

ADDENDUM TO RFP

Per our bid walk through today, here are the changes we would like inform the bidders of:

1. The MDF will be moved from M-2 to the Staff Room. All cabling from each IDF must be terminated in the Staff Room. The staff room will have the following:
 - a. New 4 port Rack will be provided by and installed by the cabling vendor. The 4 post rack will not need to be enclosed. It will be bolted to the floor and have proper cable management. It will need a key board and monitor tray.
 - b. One 220v circuit will be installed in the staff room.
 - c. All existing servers will be relocated to the Staff Room.
2. MDF Staff Room - The 10/100/1000 PoE+ port count in the new MDF is reduced from 120 to 92 ports.
3. IDF M-2
 - a. The port count in M-2 will remain unchanged at 120 ports.
 - b. The port count will be achieved by stacking (2) 48 port switches and (1) 24 port switch via stacking modules.
 - c. The Cisco 2800 router with T1 connection to the county office of educations will remain in M-2.
4. IDF R-4 will have new fiber connection to the MDF Staff Room. The BOM reflects the new 10GB Transceivers in both the MDF and IDF R-4.
5. IDF R-12 – (2) Cat6 drops will be run to R-12 from R-5. R-12 will be covered by wireless.
6. All Fiber and CAT6 Patch Cables will be provided by the cabling vendor.
1. Single mode fiber will be run to all IDF locations to support 10GB connectivity. The transceivers on the bill of materials have been changed to support 10GB over singlemode fiber.

Sincerely,

Jeremy Caudill
jcaudill@netvad.com

Netvad, Inc

1430 Blue Oaks Blvd., Ste 110
Roseville, CA 95747
916.797.2200 x222 Office
916.677.9174 Cell
916.797.2212 Fax

www.NETVAD.com